

Scope of Work Edgar Evins State Park (Ramp # 2)

1. Contractor is to remove existing floating walkway.
2. The new walkway is to be 4' wide and 60' long hinged every 10'.
3. The new walkway to be all 2" and 1-1/2" angle, all hot dip galvanized steel. 2 outriggers to accept 3'X4' float. Install 10 new 3'X4'X20" floats (use what is existing walkways also) encapsulated flotation. Decking is to be composite decking (brand: Trex Transcend, Trex Enhance, or equal) in grey color approx. 240 sq. ft. all decking is to be fasten are to be hot dipped galvanized bolts. Galvanize hand rail are to be 1 1/2" diameter 42" tall and fasten to walk way according to manufacture specs. The hinges is to be at end of each section of walk way.
4. Once the new walkway is install it must be level & stable.
5. Used existing cables and fasten to new walkway.

COURTESY DOCK(CABIN AREA)

1. Contractor is to remove existing walkway and boat slips.
2. Contractor is to install approx. 1952sq.ft. of frames. 66-3'X4'X20" floats. Anchor system with 2 dead men with 5/8" galvanized steel cables.
3. The walkway to be all 2" and 1-1/2" angle, 12" tall box frames. All frames to be hot dip galvanized steel. The walkway is to be 6' wide with 16 trusses with 4'X20' boat slips.
4. The new is to be composite decking (brand: Trex Transcend, Trex Enhance, or equal) in grey color.
5. All work must meet the Corp of Engineer specs. Contractor will be required to get all permits.
6. The contractor is to secure the work site that is in progress at all times.
7. Secure work site to prevent any unauthorized personnel from entry after hours of work in progress.
8. The contractor will be required to clean the job site on a daily basis unless eminent danger occurs which will be cleaned immediately.
9. Contractor will be responsible to repair, restore, or replace any and all damages, park at no cost to the State. Seed & straw all areas that were tore up during this project.
10. Contractor must make adequate provisions to protect park personnel and visitors through out this job.
11. All workmanship is to have a 1 year warranty dated from the date of the final inspection. And acceptance by the State.
12. The successful bidder will be required to attend a pre-construction & final inspection meeting. Contact Middle Tennessee Regional Office at (615) 797-9701 for these meetings.