Construction Bid List

This page contains all projects that are currently out for bid.

This page last updated **July 23, 2004**

Please note that all visitors to the William R. Snodgrass Tennessee Tower Building, in the Nashville Bid Region, must enter the building from the 7th Avenue Entrance and register at the Security Desk.

Bid Date Bid Time Bid Region	Project Name Project SBC No.	Brief Project Description	Designer Info.
28 July 2004 2:00 pm ET Knoxville, TN	Water System Upgrade Big Ridge State Park SBC No. 126/009-01-03	Installation of approximately 820 linear feet of 2" PVC, Schedule 40, Transmission Main, 8,760 linear feet of 6" PVC, SDR 21 Transmission Main, 4,550 linear feet of 8" PVC, SDR 21 Transmission Main, Repair, Cleaning, Repainting of the Ground Storage Water Tank, and associated incidentals and appurtenances.	Vaughn & Melton (Tennessee), Inc. (865) 546-5800 Contact: Kent Olson \$250.00 Document Deposit
29 July 2004 2:00 pm CT Nashville, TN.	Workbase Equip't Shed Yanahli WMA Maury Co., Tennessee SBC No. 220/018-02-03	Construct approx: 5040 square foot preengineered metal building with metal panel walls and roof with a 15'x24' lean-to with approx: 24'x60' of building will be finished office, toilet room and workshop, 60'x60' of building will be unfinished storage area with gravel floor.	Larry Woods and Associates (615) 383-1882 Contact: Jason Hutcherson \$250.00 Document Deposit
4 August 2004 2:00 pm CT Jackson, TN.	Humboldt Hatchery Shed Humboldt, Tennessee SBC No. 220/017-02-03	Construct approx: a 40'x60'x15' low side, single slope, pre-engineered metal building shed with 26 gauge metal siding and roofing.	TLM Associates, Inc. (731) 988-9840 Contact::Dan Nichols \$200.00 Document Deposit
11August 2004 2:00 pm CT Jackson, TN.	Re-roof / Waterproof Walls & Interior Repairs Labor & Workforce Development Center Dyersburg, Tennessee SBC No. 300/000-01-03	Tear off existing roofing and roof insulation; remove and re-install roof-mounted mechanical equipment; install new single-ply membrane roof and roof insulation on existing roof deck; replace existing sheet metal flashings and scuppers; and new scuppers, conductor heads and downspouts; clean and tuckpoint brick masonry, and minor repairs to building interior.	Clark Dickson Associates (901) 272-9250 Contact:: Larry Clark \$150.00 Document Deposit

11 August 2004 3:00 pm CT Jackson, TN.	Re-roof Project for Barracks Complex Volunteer Training Site, TNANG Lavinia, Tennessee SBC No. 368/031-01-04	Install new 25 year shingles over buildings indicated on Drawings. Work to include replacement of any damaged wood, removal of turbine vents and the installation of new ridge vents.	Military Department (615) 313-2616 Contact: Kirby Shelton \$100.00 Document Deposit
17 August 2004 2:00 pm CST Nashville, TN.	Building 681 & 682 Fire Suppression System Volunteer Training Site Smyrna, Tennessee SBC No. 361/079-01-02C	Connection to an existing water main and installation of new water main used for fire protection. Construction of a new fire pump building, installation of an electric fire pump system. Installation of a closed head foam fire suppression system, wet pipe automatic sprinklers and fire alarm system in buildings 681 and 682 North.	Smith Seckman Reid (615) 460-0455 Contact: Mike Griffin \$100.00 Document Deposit
17 August 2004 2:00 pm ET Tr-Cities, TN.	Re-roof Various Buildings Greene Valley Devel. Center Greenville, Tennessee SBC No. 344/007-01-03	Re-roof various buildings on campus to include: Remove existing ballasted system. Demolish & dispose of existing roofing material down to structural deck and associated flashing. Install new fully-adhered single-ply membrane roofing system & associated flashing. Remove asbestos containing material as outlined in survey.	Ken Ross Architects, Inc. (423)-929-2191 Contact: Richard Mason \$200.00 Document Deposit
26 August 2004 2:00 pm ET Chattanooga, TN.	Boiler Replacement Taft Youth Dev. Cntr Pikeville, Bledsoe County, Tennessee SBC No. 144/005-02-03	Demolish and replace 3 boilers, 1 deaerator, 3 boiler feed pumps, 2 #2 oil pumps, condensate return tank with 2 pumps, and all associated ducts, flues, steam piping, feedwater piping, gas and #2 oil piping, in the boiler plant. Also demolish brick stack outside.	MEP Engineering (423) 266-2821 Contact:Malcolm Newsom \$200.00 Document Deposit
26 August 2004 3:00 pm ET Chattanooga, TN.	Water Tank Addition Taft Youth Dev. Cntr Pikeville, Bledsoe County, Tennessee SBC No. 144/005-01-03	Provide a new 1,000,000 gallon bolted steel water storage tank complete with foundation slab designed by manufacturer. Provide piping and valves to connect to existing water system and tanks.	MEP Engineering (423) 266-2821 Contact:Malcolm Newsom \$200.00 Document Deposit
2 September 2004 2:00 pm CST Nashville, TN.	Reroof Engineering Building Clover Bottom Development Center Nashville, Tennessee SBC No. 344/003-02-03	Remove existing roofing and insulation down to deck and install new insulation, single-ply EPDM roofing, gravel guards and coping. Remove and replace roof shingles.	Pitts & Associates (615) 298-4097 Contact: Eula Pitts \$200 Document Deposit